

## CLADDING AND FALSE CEILINGS

### ONE COAT MORTARS CLADDINGS

**LIME MORTAR:** On the support has been extend a lime mortar rendering, to remove the imperfections. 4 hours later, over this base has been extend a finishing façades mortar, aerial lime too, with 8 cm. thickness, making the surface as uniform as is possible. The finishing is stucco, for that, other layer of aerial lime mortar has been extended to get a smooth, shine and waterproof surface, with a scraper.

**CEMENT MORTAR:** On the support has been extended a rendering regulated pigmented cement mortar of 10-15 mm thickness to assure the waterproof. 1 or 2 hours later, with a hard brush is given the finishing.

**CEMENT MORTAR WITH SPRAYED AGGREGATE:** On the support, the aggregate has been sprayed. It will begin the crushed with a trowel when it can nail into the mass. Once it is crushed, it will be smooth again with the trowel.